HVAC SYMBOL LEGEND

SYMBOL	DESCRIPTION
	-CEILING DIFFUSER, ROUND NECK (CEILING DIFFUSERS ARE 4-WAY THROW UNO)
	-CEILING EXHAUST
	-SUPPLY REGISTER OR GRILLE (VERTICAL MOUNT, SIDEWALL)
	-REVISION REFERENCE
1 M-1	-DETAIL REFERENCE: TOP-DETAIL#, BOTTOM-DRAWING# SHOWN ON
	-CONNECT TO EXISTING
	-DEMOLISH TO POINT INDICATED
	-FIRE DAMPER (WITH ACCESS PANEL)
	-DOOR GRILLE
UC	-UNDERCUT DOOR
24x12	-NEW DUCTWORK, FIRST DIMENSION IS SIDE SHOWN
24x12	-EXISTING DUCTWORK TO REMAIN
24x12	-EXISTING DUCTWORK TO BE REMOVED
	-RECTANGULAR DUCT SECTION UP, POSITIVE PRESSURE, SUPPLY OR OUTSIDE AIR
	-RECTANGULAR DUCT SECTION UP, NEGATIVE PRESSURE, RETURN
	-RECTANGULAR DUCT SECTION UP, EXHAUST
UP DN	-CHANGE OF ELEVATION
	-FLEXIBLE DUCT
	-TRANSITION, CONCENTRIC
	-TRANSITION, ECCENTRIC
10x8 8Ø	-TRANSITION, SQUARE TO ROUND
	-SQUARE THROAT ELBOW W/TURNING VANES
	-RADIUS ELBOW
	-RECTANGULAR/ROUND BRANCH TAKE-OFF OR ROUND/ROUND BRANCH TAKE-OFF
	-RECTANGLE-TO-ROUND TAKE-OFF
	-STANDARD BRANCH TAKE-OFF
	-SPIN-IN TAKE-OFF

NOTE: SOME SYMBOLS SHOWN ON THIS LEGEND MAY NOT PERTAIN TO THIS PROJECT

HVAC ABBREVIATIONS

SYMBOL	DESCRIPTION	SYMBOL	DESCRIPTION
AFD	–ADJUSTABLE FREQUENCY DRIVE	LD	–LINEAR DIFFUSER
AFF	–ABOVE FINISHED FLOOR	MBH	–THOUSAND BTUs PER HOUR
AFR	–ABOVE FINISHED ROOF	MCA	–MINIMUM CIRCUIT AMPS
AHU	–AIR HANDLING UNIT	MOCP	–MAXIMUM OVER CURRENT PROTECTION
AP	–ACCESS PANEL	MOD	–MOTOR OPERATED CONTROL DAMPER (MOD)
BOP	–BOTTOM OF PIPE	NC	–NORMALLY CLOSED
BHP	–BRAKE HORSEPOWER	NO	–NORMALLY OPEN
BTU	–BRITISH THERMAL UNIT	NTS	–NOT TO SCALE
℄	–CENTER LINE	OA	–OUTSIDE AIR
∮	–CFM (CUBIC FEET PER MINUTE)	OAL	–OUTSIDE AIR LOUVER
CD	–CEILING DIFFUSER	PRV	–PRESSURE REDUCING VALVE
CT	–COOLING TOWER	PRS	–PRESSURE REDUCING STATION
CV	–CONSTANT AIR VOLUME	PSI	–POUNDS PER SQUARE INCH
ΔP	–CHANGE IN PRESSURE	PSIG	–PSI GAUGE
ΔT	–CHANGE IN TEMPERATURE	PTAC	–PACKAGED TERMINAL AIR CONDITIONER
CFM	–CUBIC FEET PER MINUTE	PVC	–POLYVINYL CHLORIDE PIPE
CU	–CONDENSING UNIT	RA	–RETURN AIR
DDC	–DIRECT DIGITAL CONTROLS	RHC	–REHEAT COIL
DN	–DOWN	RHP	–ROOFTOP HEAT PUMP
EAT	–ENTERING AIR TEMPERATURE	RPM	–REVOLUTIONS PER MINUTE
ESP	–EXTERNAL STATIC PRESSURE	RS/L	–REFRIGERANT SUCTION & LIQUID LINES
EWT	–ENTERING WATER TEMPERATURE	RTU	–ROOFTOP AIR HANDLING UNIT
FCU	–FAN COIL UNIT	SA	–SUPPLY AIR
FD	–FIRE DAMPER	SP	–STATIC PRESSURE
FF	–FINAL FILTERS	TSP	–TOTAL STATIC PRESSURE
FLA	–FULL LOAD AMPS	UNO	–UNLESS NOTED OTHERWISE
FPM	–FEET PER MINUTE	V/PH	–VOLTS/PHASE
GPM	–GALLONS PER MINUTE	VAV	–VARIABLE AIR VOLUME
KW	–KILOWATT	VFD	–VARIABLE FREQUENCY DRIVE
LAT	–LEAVING AIR TEMPERATURE		
LWT	–LEAVING WATER TEMPERATURE		

HVAC DRAWING INDEX

SHEET	DESCRIPTION	ISSUED
M101	HVAC LEGEND, GENERAL NOTES, SHEET INDEX, AND SCHEDULES	Yes
M102	HVAC DETAILS AND SPECIFICATIONS	Yes
M111	HVAC PLAN NEW/DEMO	Yes

HVAC EQUIPMENT TAGS

TAG: A 200 CFM — -AIR DISTRIBUTION DEVICE

AHU NUMBER: AHU-1 — -AIR HANDLING UNIT

AHU NUMBER: EDH-1-1 — HEATER NUMBER — -ELECTRIC DUCT HEATER

VARIABLE/CONSTANT AIR VOLUME TERMINAL UNITS

TERMINAL UNIT TYPE:
VTU - VARIABLE TERMINAL UNIT
CTU - CONSTANT TERMINAL UNIT
PTU - PARALLEL TERMINAL UNIT
STU - SERIES TERMINAL UNIT

VTU-1-1 — AHU NUMBER — TERMINAL NUMBER

HVAC GENERAL NOTES

1. CONNECTION TO EQUIPMENT SHALL BE VERIFIED WITH MANUFACTURER'S CERTIFIED DRAWINGS. TRANSITIONS TO ALL EQUIPMENT SHALL BE VERIFIED AND PROVIDED FOR EQUIPMENT FURNISHED.
2. DIMENSIONS SHALL BE FIELD-VERIFIED AND COORDINATED PRIOR TO PROCUREMENT OR FABRICATION. COORDINATE THE WORK WITH OTHER TRADES INVOLVED. FIELD MODIFICATIONS SUCH AS OFFSETS IN PIPING OR DUCTWORK (INCLUDING DIVIDED DUCTWORK) NEEDED DUE TO OBSTRUCTIONS OR INTERFERENCES SHALL BE PROVIDED AT NO ADDITIONAL COST. FOR PROJECTS INVOLVING RENOVATION, COORDINATE NEW WORK WITH EXISTING ELEMENTS SUCH AS THE BUILDING STRUCTURE AND ARCHITECTURAL FEATURES, SPRINKLER PIPING, LIGHTS, PLUMBING, AND ELECTRICAL CONDUIT.
3. DUCT CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE SMACNA HVAC DUCT CONSTRUCTION STANDARD.
4. SEE SPECIFICATIONS FOR GAUGES, THICKNESS, BRACING, REQUIREMENTS, ETC., OF DUCTWORK.
5. PROVIDE AIR TURNING VANES IN ALL 90 DEGREE RECTANGULAR DUCT ELBOWS.
6. DUCT SIZES AND ALL OPENINGS THROUGH BUILDING CONSTRUCTION SHALL SUIT EQUIPMENT FURNISHED.
7. COORDINATE DIFFUSER, GRILLE AND REGISTER LOCATIONS WITH ARCHITECTURAL REFLECTED CEILING PLANS AND EQUIPMENT OF ALL TRADES.
8. LOCATE THERMOSTATS, TEMPERATURE SENSORS, HUMIDISTATS, AND HUMIDITY SENSORS AT 48" ABOVE FINISHED FLOOR UNLESS NOTED OTHERWISE. COORDINATE LOCATIONS WITH OTHER EQUIPMENT, FURNITURE, AND DOOR SWINGS.
9. ALL EQUIPMENT, DUCTWORK, ETC., SHALL BE SUPPORTED AS DETAILED AND/OR SPECIFIED. PROVIDE ADDITIONAL SUPPORTS AS REQUIRED TO PROVIDE A VIBRATION-FREE, RIGID INSTALLATION.
10. ALL DUCT SIZES SHOWN ARE INSIDE CLEAR DIMENSIONS.
11. DAMPERS AND INSIDES OF DUCTS VISIBLE THROUGH GRILLES, REGISTERS AND DIFFUSERS SHALL BE PAINTED FLAT BLACK.
12. REFER TO TYPICAL DETAILS FOR PIPING AND INSTALLATION OF EQUIPMENT.
13. TRAPPED CONDENSATE DRAINS FROM ALL MECHANICAL EQUIPMENT SHALL BE PROVIDED FOR PROPER DRAINAGE TO SUIT EQUIPMENT FURNISHED.
14. ACCESS PANELS IN DUCTWORK AND CEILINGS SHALL BE PROVIDED WHERE REQUIRED FOR OPERATION, BALANCING OR MAINTENANCE OF ALL MECHANICAL EQUIPMENT.
15. ALL DUCTWORK AND PIPING IS SHOWN SCHEMATICALLY. PROVIDE ALL TRANSITIONS, TURNING VANES, ELBOWS, FITTINGS, ETC., TO ALLOW SMOOTH FLOWS. ALL SPLIT DUCT FITTINGS SHALL TRANSITION TO FULL SIZE OF THE SUM OF BOTH BRANCHES, UPSTREAM OF SPLIT.
16. PROVIDE CONCRETE HOUSEKEEPING PAD UNDER ALL FLOOR-MOUNTED EQUIPMENT. REFER TO SPECIFICATIONS FOR DETAILED REQUIREMENTS.
17. VERIFY FINISH WITH ARCHITECT PRIOR TO PURCHASING GRILLES, REGISTERS, DIFFUSERS, LOUVERS AND OTHER AIR DISTRIBUTION DEVICES.
18. PROVIDE FLEXIBLE DUCT CONNECTIONS ON ALL DUCTWORK CONNECTING TO EACH FAN, AIR HANDLING UNITS, AND FAN COIL UNITS.
19. PROVIDE TRANSITIONS AT DIFFUSER NECKS AS REQUIRED TO MATCH SIZES OF FLEX DUCTS TO BE CONNECTED.
20. INTERRUPTIONS TO EXISTING SERVICES SHALL BE SCHEDULED FOR TIMES OTHER THAN NORMAL OPERATING HOURS (SUCH AS NIGHTS AND WEEKENDS). SUCH INTERRUPTIONS TO SERVICES SHALL NOT BE MADE WITHOUT THE PRIOR WRITTEN CONSENT OF THE OWNER'S REPRESENTATIVE AND PROPER COORDINATION WITH OTHER TRADES. PRE-WORK SHALL BE PERFORMED TO MAKE THE SHUTDOWN PERIOD AS BRIEF AS POSSIBLE.
21. ALL EQUIPMENT, DUCTWORK, ETC., TO BE REMOVED SHALL REMAIN PROPERTY OF THE OWNER OR DISPOSED OF LEGALLY, AS DIRECTED BY OWNER.
22. MAINTAIN CLEARANCE OF A MINIMUM OF 6" BETWEEN DUCTWORK, PIPING, EQUIPMENT, ETC., AND ALL FIRE RATED AND FIRE/SMOKE RATED PARTITIONS, TO ALLOW FOR INSPECTIONS OF RATED WALLS.
23. LOCATE ALL OUTSIDE AIR INTAKES A MINIMUM OF 10'-0" CLEAR FROM ALL PLUMBING VENTS AND EXHAUST AIR DISCHARGE LOCATIONS. LOWEST POINT OF EACH OUTSIDE AIR INTAKE ON ROOF SHALL BE A MINIMUM OF 24" ABOVE ROOF.
24. DUCT RUNOUTS TO DIFFUSERS SHALL MATCH THE SIZE OF THE DIFFUSER NECK.
25. WATER PRESSURE DROPS THROUGH COIL CONTROL VALVES SHALL NOT EXCEED 5 PSI.
26. UNLESS OTHERWISE NOTED, ALL EQUIPMENT AND VALVE DRAINS SHALL BE INDEPENDENTLY PIPED FULL SIZE TO THE NEAREST PLUMBING DRAIN.
27. SLEEVE AND SEAL ALL PIPING PENETRATIONS THROUGH BUILDING PARTITIONS. PROVIDE MANUAL AIR VENTS AT ALL HIGH POINTS IN CHILLED WATER AND HOT WATER PIPING.

ORANGE CO. BLDG. DEPT. NOTES

1. SHEET METAL DUCTWORK (ALL): PRIME QUALITY 48 INCH WIDE RESQUARE TIGHT COAT COLD-ROLLED HOT-DIPPED GALVANIZED STEEL CAPABLE OF DOUBLE SEAMING WITHOUT FRACTURE. CONFORM TO THE REQUIREMENTS OF ASTM A-525 AND ASTM-G90 FOR A MINIMUM GALVANIZING COAT OF 1.25 OUNCES PER SQUARE FOOT TOTAL FOR BOTH SIDES. (REFER TO SPECIFICATION ON DRAWING M.1-3)
2. INSULATE ALL SUPPLY DUCTWORK WITH A MINIMUM OF 2" (R=4.2 MINIMUM) THICK FIBERGLASS BLANKET WRAP. INSULATION SHALL BE APPLIED WITH EDGES TIGHTLY BUTTED, VAPOR RETARDANT FACING OVERLAPPED A MINIMUM OF 2", AND ALL JOINTS AND BREAKS IN THE VAPOR RETARDANT SEALED USING GLASS FABRIC AND MASTIC APPLIED IN CONFORMANCE WITH THE MANUFACTURER'S RECOMMENDATIONS.
3. ALL AHU'S SHALL BE STOPPED UPON FIRE ALARM ACTIVATION (& SMOKE DETECTOR/FIRESTAT IN R.A), UNLESS PART OF AN ENGINEERED SMOKE CONTROL SYSTEM.
4. ALL PLENUM SPACES / CHAMBERS SHALL BE IN COMPLIANCE WITH THE FLORIDA MECHANICAL CODE.
5. ALL DUCT SUPPORTS SHALL BE 1½" WIDE, MINIMUM.
6. PIPING SHALL BE SUPPORTED BY SUBSTANTIAL NON COMBUSTIBLE HANGERS TO PERMIT MOVEMENT DUE TO THERMAL EFFECTS WITHOUT UNDUE STRAIN ON THE RUN.
7. A PERMANENT FACTORY-APPLIED NAMEPLATE(S) SHALL BE AFFIXED TO APPLIANCES ON WHICH APPEAR LEGIBLE LETTERING, THE MANUFACTURER'S NAME OR TRADEMARK, THE MODEL NUMBER, SERIAL NUMBER AND THE SEAL OR MARK OF THE APPROVED AGENCY, AS REQUIRED BY THE FLORIDA BUILDING CODE, MECHANICAL SECTION 301.
8. HYDRONIC PIPE INSTALLED IN BUILDINGS SHALL CONFORM TO THE REQUIREMENTS AS SET FORTH IN CHAPTER 13 OF THE FLORIDA BUILDING CODE. INSULATION SHALL BE TESTED IN ACCORDANCE WITH ASTM E 84 AND SHALL HAVE A MAXIMUM FLAME SPREAD INDEX OF 25 AND A SMOKE DEVELOPED INDEX NOT EXCEEDING 450. REFERENCE MECHANICAL SPECIFICATIONS, SECTION 15250 FOR COMPLETE REQUIREMENTS.
9. CLEARANCES AROUND MECHANICAL EQUIPMENT TO ELEMENTS OF PERMANENT CONSTRUCTION, INCLUDING OTHER INSTALLED EQUIPMENT AND APPLIANCES, SHALL BE SUFFICIENT TO ALLOW INSPECTION, SERVICE, REPAIR OR REPLACEMENT WITHOUT REMOVING SUCH ELEMENTS OF PERMANENT CONSTRUCTION OR DISABLING THE FUNCTION OF A REQUIRED FIRE-RESISTANCE RATED ASSEMBLY.

TABLE 4-1
RECTANGULAR DUCT HANGERS MINIMUM SIZE

MAXIMUM HALF OF DUCT PERIMETER	PAIR AT 10 FT SPACING		PAIR AT 8 FT SPACING		PAIR AT 5 FT SPACING		PAIR AT 4 FT SPACING	
	STRAP	WIRE/ ROD	STRAP	WIRE/ ROD	STRAP	WIRE/ ROD	STRAP	WIRE/ ROD
P/2 = 30"	1"x 22 GA.	10 GA. (.135")	1"x 22 GA.	10 GA. (.135")	1"x 22 GA.	12 GA. (.106")	1"x 22 GA.	12 GA. 106")
P/2 = 72"	1"x 18 GA.	3/8"	1"x 20 GA.	1/4"	1"x 22 GA.	1/4"	1"x 22 GA.	1/4"
P/2 = 96"	1"x 16 GA.	3/8"	1"x 18 GA.	3/8"	1"x 20 GA.	3/8"	1"x 22 GA.	1/4"
P/2 = 120"	1½" x 16 GA	1/2"	1"x 16 GA.	3/8"	1"x 18 GA.	3/8"	1"x 20 GA.	1/4"
P/2 = 168"	1½" x 16 GA	1/2"	1½" x 16 GA	1/2"	1"x 16 GA.	3/8"	1"x 18 GA.	3/8"
P/2 = 192"	NOT GIVEN	1/2"	1½" x 16 GA	1/2"	1"x 16 GA.	3/8"	1"x 16 GA.	3/8"
P/2 = 193" UP	SPECIAL ANALYSIS REQUIRED							

WHEN STRAPS ARE LAP JOINED USE THESE MINIMUM FASTENERS:

1"x 18, 20, 22 GA.-TWO #10 OR ONE 1/4" BOLT
1"x 16 GA.-TWO 1/4" DIA.
1 1/2"x 16 GA. -TWO 3/8" DIA.
PLACE FASTENERS IN SERIES, NOT SIDE BY SIDE.

SINGLE HANGER MAXIMUM ALLOWABLE LOAD	
STRAP	WIRE OR ROD (DIA.)
1"x 22 GA.-260 LBS.	0.016"-.80 LBS.
1"x 20 GA.-320 LBS.	0.135"- 120 LBS.
1"x 18 GA.-420 LBS.	0.162"- 160 LBS.
1"x 16 GA.-700 LBS.	1/4"- 270 LBS.
1 1/2"x 16 GA. -1100 LBS.	3/8"- 680 LBS.
	1/2"- 1250 LBS.
	5/8"- 2000 LBS.
	3/4"- 3000 LBS.

NOTES
1. DIMENSIONS OTHER THAN GAGE ARE IN INCHES.
2. TABLES ALLOW FOR DUCT WEIGHT, 1 LB./SF INSULATION WEIGHT AND NORMAL REINFORCEMENT AND TRAPEZE WEIGHT, BUT NO EXTERNAL LOADS.
3. FOR CUSTOM DESIGN OF HANGERS, DESIGNERS MAY CONSULT SMACNA'S RECTANGULAR INDUSTRIAL DUCT STANDARDS, THE AISI COLD FORMED STEEL DESIGN MANUAL, AND THE AISC STEEL CONSTRUCTION MANUAL.
4. STRAPS ARE GALVANIZED STEEL; OTHER MATERIALS ARE UNCOATED STEEL.
5. ALLOWABLE LOADS FOR P/2 ASSUME THAT DUCTS ARE 16 GA. MAXIMUM, EXCEPT THAT WHEN MAXIMUM DUCT DIMENSION (W) IS OVER 60" THEN P/2 MAXIMUM IS 1.25W.
6. FOR UPPER ATTACHMENTS REFER TO SMACNA DUCT STANDARDS - SECOND EDITION: FIG. 4-2
7. FOR LOWER ATTACHMENTS REFER TO SMACNA DUCT STANDARDS - SECOND EDITION: FIG. 4-4
8. FOR TRAPEZE SIZES REFER TO SMACNA DUCT STANDARDS - SECOND EDITION: TABLE 4-3 AND FIG. 4-5.
9. 12, 10, OR 8 GA. WIRE IS STEEL OF BLACK ANNEALED, BRIGHT BASIC, OR GALVANIZED TYPE.

COPYRIGHT: HVAC DUCT CONSTRUCTION STANDARDS METAL AND FLEXIBLE - SECOND EDITION.

TABLE 4-2
MINIMUM HANGER SIZES FOR ROUND DUCT

DIA.	MAXIMUM SPACING	WIRE/ DIA.	ROD	STRAP
10" DN. 250 MM DN	12' 3.7 M	ONE 12 GA. ONE 2.75 MM	1/4" 6.4 MM	1"x 22 GA. 25.4 x 0.85 MM
11-18"	12'	TWO 12 GA. OR ONE 8 GA.	1/4"	1"x 22 GA.
460 MM	3.7 M	ONE 4.27 MM	6.4 MM	25.4 x 0.85 MM
19-24" 610 MM	12' 3.7 M	TWO 10 GA. TWO 3.51 MM	1/4" 6.4 MM	1"x 22 GA. 25.4 x 0.85 MM
25-36" 900 MM	12' 3.7 M	TWO 8 GA. TWO 2.7 MM	3/8" 9.5 MM	1"x 20 GA. 25.4 x 0.85 MM
37-50" 1270 MM	12' 3.7 M	————	TWO 3/8" TWO 9.5 MM	TWO 1"x 20 GA. (2) 25.4 x 1.00 MM
51-60" 1520 MM	12' 3.7 M	————	TWO 3/8" TWO 9.5 MM	TWO 1"x 18 GA. (2) 25.4 x 1.31 MM
61-84" 2130 MM	12' 3.7 M	————	TWO 3/8" TWO 9.5 MM	TWO 1"x 16 GA. (2) 25.4 x 1.61 MM

NOTES
1. STRAPS ARE GALVANIZED STEEL; RODS ARE UNCOATED OR GALVANIZED STEEL; WIRE IS BLACK ANNEALED, BRIGHT BASIC, OR GALVANIZED STEEL. ALL ARE ALTERNATIVES
2. REFER TO SMACNA DUCT STANDARDS - SECOND EDITION: FIG. 4-4 FOR LOWER SUPPORTS.
3. REFER TO SMACNA DUCT STANDARDS - SECOND EDITION: FIG. 4-2 AND 4-3 FOR UPPER ATTACHMENTS.
4. TABLE ALLOWS FOR CONVENTIONAL WALL THICKNESS, AND JOINT SYSTEMS PLUS ONE LB/SF INSULATION WEIGHT. IF HEAVIER DUCTS ARE TO BE INSTALLED, ADJUST HANGER SIZES TO BE WITHIN THEIR LOAD LIMITS; REFER TO SMACNA DUCT STANDARDS - SECOND EDITION ALLOWABLE LOADS WITH TABLE 4-1. HANGER SPACING MAY BE ADJUSTED BY SPECIAL ANALYSIS.
5. DESIGNERS: FOR INDUSTRIAL GRADE SUPPORTS, INCLUDING SADDLES, SINGLE LOAD TRAPEZE LOADS, LONGER SPANS AND FLANGE JOINT LOADS, SEE SMACNA'S ROUND INDUSTRIAL DUCT CONSTRUCTION STANDARDS.
6. REFER TO SMACNA DUCT STANDARDS - SECOND EDITION: FIGS.3-9 AND 3-10 FOR FLEXIBLE DUCT SUPPORTS.

COPYRIGHT: HVAC DUCT CONSTRUCTION STANDARDS METAL AND FLEXIBLE - SECOND EDITION

FAN SCHEDULE

PLAN MARK	MODEL NO.	TYPE	CFM	STATIC PRESS.	FAN RPM	MOTOR RPM	MOTOR HP	VOLT/ PHASE	DRIVE TYPE	FAN SERVICE	ACCESSORIES
EF/L-1	BROAN	EXHAUST FAN LIGHT COMBO	50	.125	-	-	-	120/1	DIRECT	TOILET EXHAUST	24,25

ACCESSORIES
1) BACKDRAFT DAMPER
2) THERMOSTAT
3) BIRDSCREEN
4) ROOF CURB
5) DISCONNECT SWITCH
6) DRAIN
7) EQUIPMENT SUPPORTS
8) INLET SCREEN
9) CURB MOUNT ROOF JACK
10) SPEED CONTROLLER
11) WALL SHUTTER
12) VIBRATION ISOLATORS
13) WALL CAP
14) WALL SHUTTER - MOTORIZED
15) WEATHER COVER
16) 2 SPEED / 1 WINDING
17) FILTERS
18) WALL COLLAR
19) FAN GUARD/SCREEN
20) COMPANION FLANGES
21) INSULATED HOUSING FOR SOUND CONTROL
22) HINGED FRAMES
23) SPARK/EXPLOSION PROOF
24) LIGHT & EXHAUST FAN TO BE ACTIVATED BY LIGHT SWITCH
25) UNIT DRAWS 2.0 AMPS

NOTES:
1. MODEL NUMBERS AND FAN SELECTION ARE BASED ON GREENHECK.

TLC ENGINEERING FOR ARCHITECTURE
1717 S. Orange Avenue
Suite 300
Orlando, Florida 32806
Phone: 407-841-9250
Fax: 407-425-7367
www.tlc-engineers.com
© Copyright 2005 TLC Engineering for Architecture, Inc.
EB #0000015 TLC NO: 106047

SEAL

Edward J. Carroll, P.E.
Florida License #62802
Seal

PRINCETON HOUSE CHARTER SCHOOL
ORLANDO, FLORIDA

HuntonBrady ARCHITECTS

DATE	SUBMISSION / REVISION	NO.

HVAC LEGEND, GENERAL NOTES, SHEET INDEX, AND SCHEDULES

PROJ. NO. 010100 SHEET
DRAWN RNC
M101

Copyright HuntonBrady Architects P.A. All Rights Reserved. 800 N. Magnolia Ave., Suite 600, Orlando, Florida 32803 (407) 839-0886 (407) 839-1709/Fax www.huntonbrady.com License AAC001744

M:\2006-Jobs\106047-Princeton House School 2008\CAD-MEP\Sheets\ M101.dwg 06/13/06 07:59 luke.vordanian-999999999